Transformer building

New fence

New pipeline from Nieuwehorne

VSD and PLCs Room 3x5.5x4

Compressor Package 10x 5.5x5

Swing gate

Emergency Exit

Air coolers 1xfan D=2,8 m

Liquid Pumps

Inlet separator

existing pipeline 10" 17-OLD-10-S-5000

10" Pig Launcher 5000-DG-600

6" 6"

Drain Pit

Vent Pit

6" Pig Reciever 5000A-DG-100

10"

6" Pig Reciever 5008-DG-200

10" Pig Reciever 5000-DG-300

Sliding gate

existing pipeline 10" 17-OLD-10-S-5000

Enterance Sliding gate

10" Pig Reciever 5000-DG-400

Border land use plan

New fence

existing pipeline 6" 88-VKG-6-S-5008

existing pipeline 6" 15-WSF1-6-S-5000A

VIEW LOOKING WEST

TRUE NORTH

PLANT NORTH

REV.	DATE	DESCRIPTION	DRWN	CHK'D	APPR
0A1	11-08-2016	RE-ISSUE FOR PERMITTING	SAH	SN	DA
0	04-07-2016	ISSUED FOR PERMITTING	SAH	SN	DA

LOCATION: MILDAM

WELLS:

VERMILION ENERGY

TITLE: PLOTPLAN

REF. No.: -

CAD No: -

SCALE:	SIZE	DRAWING NUMBER:	SHEET:
1 : 200	A0	1-32-JM001-3-32-001	001